

STAFF MEMBERS

Hector Ruiz, General Manager
Michael Perca, District Secretary
Cindy Byerrum, District Treasurer
Bowie, Arneson, Wiles & Giannone,
District General Legal Counsel



BOARD OF DIRECTORS

Stephen Dopudja, President
Glenn Acosta, Vice President
Don Chadd, Director
Edward Mandich, Director
Michael Safranski, Director

**Addendum No. 2
To Contract Documents and Specifications**

For

**Alternate Raw Water Transmission Line
FEMA-1952-DR-CA CA OES ID:059-91099**

Project No. 6177

November 23, 2016

This addendum is hereby made part of the Contract Documents and Specifications. Receipt of the Addendum shall be noted on the Bid Form. The following changes, additions, clarifications, or modifications shall be made to the Contract Documents and Specifications; all other conditions remain the same.

BID DOCUMENTS

BID FORM, Page 3 of 14

SCHEDULE OF WORK ITEMS: 2-Inch Air/Vacuum Valve, ITEM No. 13

DELETE Estimated Quantity of "2"

REPLACE with

Estimated Quantity of "3"

GENERAL REQUIREMENTS

SECTION 01010 Summary of Work

SECTION 1.05: PHASING OF THE WORK, Item D

DELETE D in its entirety and **REPLACE** with the following:

"D. Abandonment and removal of the existing 16-inch pipeline:

1. All pipe exposed over Serrano Creek shall be removed. The Contractor shall prepare a plan for the removal of the exposed pipe. Access into the Serrano Creek shall only be performed by foot. Any equipment shall be hand carried, if required. No clearing or grubbing will be allowed near or around the creek and work needs to be performed from the existing access roads.
2. The portion of existing pipeline abandoned in place shall be filled and capped with slurry per section 01045.
3. The portion of existing pipeline exposed over Serrano Creek shall be removed with equipment which will not cause any damage to the surrounding habitat and vegetation. The aboveground portion of the existing pipeline shall be removed. The use of equipment resulting in clearing and grubbing within the Serrano Creek, surrounding embankment, or bluff areas is prohibited. Refer to the environmental mitigation measures in Appendix H and Spec Section 01045 for additional requirements.
4. Pipe removal within the creek shall be scheduled outside of the nesting season (August 1 to February 15). If work cannot be done outside of nesting season, Contractor shall coordinate with TCWD to do the work within nesting season (February 16 to July 31) upon TCWD's receipt of approval from the regulatory agencies, including US Army Corp Of Engineers..

PLANS

Sheet C-102, DELETE

Note 27, 16" Butterfly Valve at Station 23+40.00 and

ADD

Note 27, 16" Butterfly Valve at Station 23+75.00

Sheet C-104, ADD

Note 10, 2" Air/Vacuum Valve at Station 46+20.00

END OF ADDENDUM NO. 2



Lorrie Lausten, P.E.
Engineer

November 23, 2016